FIREDOORS

NINZ S.p.A. - corso Trento, 2/A I-38061 ALA (TN) / ITALY <u>www.ninz.it</u> Tel. + 39 0 464 678300 Fax. +39 0 464 679025 info@ninz.it

# **EXUS LP BC**

# PANIC EXIT DEVICE for emergency exits

Protrusion of the exit bar: 125mm.

RECOMMENDATIONS

A052-GB

5001149/2 - 07/17

	Commercial codes		DoP no.	1125-TW-EX-01
	EXUS LP BC	item 4201101.005	Website	https://www.ninz.it/it/download/dop
			Classification	3 7 7 B 1 3 2 1 A A
	Name and address of the producer	NINZ S.p.A corso Trento 2/A I-38061 ALA (TN) - ITALIA	-	- Category of use: high frequency
	Year application trademark	2007	3rd Character - grade 7	- Durability: 200.000 cycles - Mass of the door: over 200kg - Suitable for use on fire/smoke rated doors
した	Standard	EN 1125:2008 + EC1:2009	6th Character - grade 3	<ul> <li>Safety: suitable for emergency exits</li> <li>Highly resistant to corrosion 96h</li> <li>Safety of goods: 1000N</li> </ul>
	Certification authority no.	0425	8th Character - grade 1	- Protrusion of the exit bar: up to 150mm - Activation type: push bar
	CE certification no.	0425-CPR-001228	10 <sup>th</sup> Character - grade A	- Suitable for 1 or 2 leaved door
			doors up to 1350x2880m	e leaf or for the active (first opening) leaf of two-leaved $m/leaf$ in size, a mass of up to 300kg/leaf, mounted resistant up to $El_2120$ - REI120 and smoke proof.

# SYMBOLS EMPLOYED



# CAUTION

Indicates a danger that threatens people and/or material goods. Failure to observe the warnings indicated by this symbol may have serious consequences, such as personal injury and property damage.



#### ATTENTION

Indicates a danger that threatens material goods. Failure to observe the warnings indicated by this symbol may result in damage to material goods.



Warnings related to important technical aspects.

## PRODUCT DESCRIPTION

Panic bar for one-leaved doors or for the active leaf of two-leaved doors located at emergency exits and activated by push-bars. Composed of galvanized steel controls, black plastic casing and lever, horizontal aluminium bar and blank external plate.

This product does not contain or release any hazardous materials, as per UNI EN standard no. 1125 appendix ZA.

#### **OPERATION MODE**

From the pull side (blank external plate side) the door can not be opened, whereas opening is possible from the push side at any time by pushing on the horizontal bar of the EXUS LP BC panic bar.

#### WARNINGS

The EXUS panic bar activated by means of a horizontal bar is intended for use onto doors installed in escape routes where panic situations could develop.

The safety features of this product are of fundamental importance to ensure its conformity with EN 1125. It is strictly forbidden to introduce any type of modifications apart from those described in these installation instructions.

In order to ensure that the panic bar could provide a high level of safety toward people and appropriate safety level toward goods, it should only be mounted onto doors and doorframes that are in good conditions. The door itself, therefore, should be checked to ensure that it was installed properly and that nothing obstructs its normal movement.

If rebate sealing are mounted on the door, make sure they do not inhibit proper functioning of the panic bar.



In case of two-leaved door where both leaves are equipped with panic bar, it is mandatory to check that each leaf opens when its respective panic bar is activated, and that leaves open freely when the bars are activated simultaneously.

The fastening instructions in the present document should be followed scrupulously during installation. Once installation is complete, the installer should give this document to the owner of the activity.

The horizontal bar should be installed in a way that maximizes its useable length.

For securing the door in the closed position, do not employ any other latching devices than those specified in the present document. This does not preclude the installation of automatic closing devices.


Different external access devices than those found on the list of certified components on pages 4/4 are considered unacceptable.

The EXUS panic bar is also designed for installation on hollow metal doors with an internal cell structure.

If a door closer is needed to return the door to the closed position, care should be taken not to make the opening step more difficult for children, the elderly and the disabled.

A pictogram (arrow) should be positioned immediately above the horizontal bar on the internal side of the door.

All of the included components described herein must be positioned and mounted in conformity with the present document.



#### CONTENTS OF THE EXUS LP BC PANIC BAR PACKAGE

position	pcs.	description	position	pcs.	description
1, 2	01	Twist/Exus mechanism assembly	19	02	Ø15,0x23,5r
3, 4, 5	01	Twist/Exus LP carter set with plugs	20	02	Black cap ho
6	01	Exus LP set carrier arms	21	04	Pan head se
7	02	M5x10mm hex socket countersunk screw	22	01	S2 hex key
8	01	S3 hex key	26	01	Washer
9	01	Adhesive pictogram (green arrow)	27	01	S4 hex key
10	01	Horizontal bar in anodized aluminium	# 29	01	Installation p
12	01	Installation plate in galvanized steel	# 30	01	Blank cover
13	01	Blank cover plate in black plastic	# 31	02	Pan head se
14, 14a	01	9x9x40mm threaded square spindle with M5x20mm hex	# 32	02	M3x8mm pa
		socket screw	-	01	A034 hole-d
15	02	M5 threaded insert	-	01	Exus LP BC
16	02	M5 countersunk head screw			
17	06	Toothed washer (# 8 pcs. for stainless steel version)	- <del>- </del> -	The pani	c lock (24) ar
18	01	Ø10,3x60,6mm spacer	20	are deliv	ered already

 19
 02
 Ø15,0x23,5mm spacer

 20
 02
 Black cap hole Ø8,8mm

 21
 04
 Pan head self tapping screw Ø4,8x16mm

 22
 01
 S2 hex key

 26
 01
 Washer

 27
 01
 S4 hex key

 29
 01
 Installation plate in galvanized steel

 30
 01
 Blank cover plate in stainless steel

 31
 02
 Pan head self tapping screw Ø4,2x13mm

 32
 02
 M3x8mm pan head screw

 01
 A034 hole-drilling template

 01
 Exus LP BC panic bar set installation instruction

Please note that article 4 of the MD of 03 November 2004 obliges the installer to write up, sign and provide the owner of the activity with a declaration of proper installation that makes explicit reference to the instructions supplied by the exit device manufacturer.

# TOOLS REQUIRED

Medium-sized Philips-head screwdriver or electric screwdriver, electric drill with  $\emptyset$ 2 and  $\emptyset$ 3mm drill bit for steel, fine-toothed hack-saw and hack-saw for aluminium.

mounted on the door!

#### IMPORTANT

- Installation should be carried out by gualified personnel only and in strict conformity with the instructions supplied.
- For a correct installation all supplied components must be used, including spacers and toothed washers.




- No variations are allowed, and only components indicated in the package contents may be used.

- Given its purpose, the Exus LP BC panic bar should be mounted on the pushside of the door.
- Before proceeding with installation, check the package contents to ensure that no pieces are missing.
- Check if the door is equipped with the panic safe lock.
- Check the type of external plate to apply and follow the specific instructions. - Any different installation configuration from that illustrated on page 2/4 is not

#### INSTALLATION

allowed

- Adjust the plastic spacers (18 and 19) to the thickness of the leaf so that they do not protrude more than 1mm from it.
- Adjust the threaded square spindle (14) to the thickness of the leaf so that it protrudes 11±1mm from the door surface; be careful to cut the bevelled side.
- Insert the washer (26) over the square hole of the panic safe lock (24), from the pull-side of the door, as showed in drawing (28). Insert the M5x20mm screw (14a) over the washer (26) and screw it at the square spindle (14), using the S4 hex wrench (27). Make sure that washer and square spindle are correctly inserted over the square holes before tighten the screw (14a).
- In case of stainless steel BC version screw onto installation plate (29) the screws (32), just enough to insert the cover plate (30).
- Insert the two threaded inserts (15) in the installation plate (12 or 29), making sure that they are well-centred.
- Insert the two spacers (18 and 19) over the threaded inserts (15) and apply the installation plate on the pull-side of the door, being careful to center the inserts over their respective holes.
- Apply the operating mechanism (1) to the lock side (push-side of the door) after inserting the screws (16), toothed washers (17) and spacer (19). Center the square spindle and screws, starting the screws by hand before fastening them with the screwdriver.
- Use the template to drill the holes (23) with the Ø3mm drill bit, checking the level. If holes are already present, drill them again for the internal reinforcement.
- Fasten the mechanism (1) even more securely with the self-tapping screws Ø4,8x16mm (21) and their toothed washers (17).
- Fix the square spindle (14) at the operating mechanism (1), using the S2 hex wrench (22).
- Fasten the mechanism (2) of the panic bar at hinged side, using the selftapping screws Ø4,8x16mm (21) and their toothed washers (17).
- Put the plastic carter with "EXIT" wording (3) on the operating mechanism (1) and the other one (4) on the hinged side mechanism (2), snapping them on manually.
- In case of plastic BC version clip the cover plate (13) manually onto installation plate (12).
- Apply the carrier arms (6) and fasten them with the dedicated screws (7), tightening them securely with the included S3 wrench (8).
- Make a precise "L" measurement, cut the aluminium bar (10) adding 19mm and remove the burrs from the cut edge. Remove one carrier arm, attach the bar and re-fasten the entire assembly.
- Apply the plugs (5).
- Insert the two caps (20) in the open holes of the panic safe lock (24).



- In case of stainless steel BC version it is also necessary to fasten the installation plate (29) using the self-tapping screws Ø4,2x13mm (31) and their toothed washers (17) after drilling holes in the metal panel with the Ø2mm drill bit. Insert the cover plate (30) onto installation plate (drw. 2). Using the S2 hex key (22), unscrew the screws (32) until the cover become fixed, avoiding any deformation (drw. 3).
- Apply the pictogram (9) with the green arrow on the internal surface of the door, just above the horizontal bar.



- Lastly, use a dynamometer to measure the force required on the horizontal bar to release the lock. Record this force measurement in the present document.

#### USE

- Ensure that the door always opens easily.
- Avoid unnecessary strains on or handling onto external plate and exit bar.
- Protect the panic bar from external atmospheric agents.
- Ensure that nothing hinders the free movement of the horizontal bar.
- Do not paint the lock.
- Use the bar properly, do not pull it in the wrong direction.
  - Make sure that any damaged or malfunctioning parts are replaced immediately.

#### MAINTENANCE

To ensure that door usage conforms with regulations, the following maintenance checks should be carried out at least once a month:

- Confirm that all of the installed components correspond with those listed in the present instructions and that no other latching devices than those originally installed have been added to the door.
- Inspect and activate the panic bar to verify that all of its components are in satisfactory operational condition.
- Use a dynamometer to confirm that the release force shows no significant differences from the forces recorded at the time of installation.

- Check whether all screws are fully tightened, tightening any that may have loosened.

- Check whether panic bar can be moved with minimal effort, and that the latch bolt of the safe lock retreats from the strike box without offering resistance. If the door has become difficult to open due to friction, the resistance can be reduced by filing the strike box down to the appropriate height.
- Activate the Exus LP BC panic bar at both ends of the horizontal bar, checking to ensure full retraction of the latch bolt in both cases.
- Ensure that the latch bolt exits completely when the horizontal bar is released.
- Check the horizontal bar and replace it if any damage or deformities are detected.

- Check whether the inserts and strike boxes are blocked in any way and eliminate any obstructions.

- This product requires no special maintenance. Grease spray should be used to lubricate the internal workings of lock and panic bar on a regular basis - the latter has a hole on its carter for this purpose, located below the carrier arms.
- For normal cleaning use mild detergents.

↔ - Any adjustments that become necessary must be carried out by qualified personnel using original NINZ replacement parts.

The owner of the activity is responsible for keeping the declaration of correct installation on file, conducting proper panic bar maintenance in accordance with all of the manufacturer's maintenance guidelines, keeping maintenance and check-up records and preserving the present document.

0425	
	ICIM
	ICIM S.p.A Identification number: 0425 Piazza Don Enrico Mapelli, 75 - 20099 Sesto San Giovanni (MI) - ITALY
	Certificato di costanza delle prestazioni Certificate of constancy of performance
	Certificato N. Certificate No. 0425 - CPR - 001228
	In conformità el Regiotamento 355/3071ELI del Patramento Europeo e del Consiglio dei la mazo 2011 (Regiotamento Prototti da Construccio e CPR), questo contella se applica al aportetta dei construcciona in compliance with Regulation 355/2011ELI del European Patrilement endar di far Council del March 2011 (file Construction Producto Centrolicano er CPR), fuesto contellancia applica la portectamento in poducto - Producto Centrolicano er CPR, fuesto contellancia pagina la fue construction producti- contectamento entrolicano e CPR, fuesto contectamento entrolicano esta construction producti- producto Centrolicano er CPR, fuesto contectamento entrolicano esta construction producti-
	Dispositivi per le uscite antipanico azionati mediante una barra orizzontale per l'utilizzo sulle vie di esodo Panic exit devices operated by a horizontal bar, for use on escape routes setter (setters) TWIST, EXUS LP, EXUS LA, EXUS LX
	MODELLI/MODELS Si veda allegato / See annex
	Caratteristiche: vedi Allegato / Charactéristics: see Annex IMMESSO SUL MERCATO CON IL NOME O IL MARCHIO DI
	PLACED ON THE MARKET UNDER THE NAME OR TRADE MARK OF NINZ S.p.A.
	•
	SEDE LEGALE HEAD OFFICE Corso Trento, 2/A - 38061 ALA (TN) - ITALY
	UNITÀ OPERATIVA PRODUCTION UNIT Corso Trento, 2/A - 38061 ALA (TN) - ITALY
	Questo certificato attesta da fue fue disposizioni riguardanti la valutacione e la verifica della costanza della prestazione e la prestazioni destini tenellatigata 24 dalla norma: This certificato attesta tata al provisione concerning the assessment and verification of constancy of performance and the performance attendera in Anez 4.0 de tendender
	EN 1125:2008 + EC1:2009 nell'ambito del sistema 1 di cui al presente certificato vengono applicati e che il controllo di produzione in fabbrica condotto dal
	produtione è valutato al fine di garantine la under system 1 set out in this certificate are applied and that the factory production control conducted by the manufacturer is assessed
	to ensure the COSTANZA DELLA PRESTAZIONE DEL PRODOTTO DA COSTRUZIONE CONSTANCY OF PERFORMANCE OF THE CONSTRUCTION PRODUCT
	Questo cartificato è state messo per la prima volta il 1904/2007 e la validità sino a che la norma amenozzata, il prodotto da costructoria, interito AL/OP de condicioni o fonzicone nello statiliamento no subascano modificate significative, o sino a che non rivega sospesso rinterito dall'organismo di conflicazione collettani LOM Sig. A This conflictate vanti ci audio di 1904/2007 and vil remani validi a lorgi an refine the hamonolesi stimodari, the construction product, fle AVCP methodis no the manufacturing conditions in the plant are modified significantly, uniess suspended or withdrawn by the conflictate valicativation of Social Sig. A
	Il presente Certificato é da ritenensi valido solo se accompagnato dal relativo Allegato / This Certificate is valid only with the relative Annex
	<u> </u>
	Direttore Tecnico
	EMISSIONE ISSUE
	22/06/2017
	ICIM S.p.A Piazza Don Enrico Mapelli, 75 - 20099 Sesto San Giovanni (Mi)

	SPARE PARTS (see exploded drawing at page 2/4)				
	position	code	description		
	1, 2, 3, 4, 5, 6, 7, 8, 9	3102055.001	Exus LP latch case – black plastic		
	1, 2	3105113.001	Twist/Exus assembly mechanism		
	3, 4, 5	3105104.001	Twist/Exus LP carter set with plugs		
	6	3105123.001	Exus LP carrier arm set		
	7, 8	3105026.001	Twist/Exus bag		
	10	4204009	Anodized or painted aluminium bar set		
	8, 12, 13, 14, 14a, 15, 16, 17, 18, 19, 20, 21, 22, 26, 27	4211101.005	Twist/Exus BC set - black plastic		
#	8, 14, 14a, 15, 16, 17, 18, 19, 20, 21, 22, 26, 27, 29, 30, 31, 32	4211101.025	Twist/Exus BC set - stainless steel		
	24	3201001.016	Panic safe lock to push (AP 16/18)		
	25	4212024.001	Set of 10 Proget strike box lock		
	25	4212025.001	Set of 10 Univer thk60 strike box lock		
	25	4212026.001	Set of 10 Univer thk50 strike box lock		
	25	4212027.001	Set of 10 Rever strike box lock		

Certified components for EXUS LP BC

Panic exit device:	model "EXUS LP"
Panic safe lock:	item AP 16/18
Lock strike boxes:	items 2401006, 2401005, 2401015, 2401014
Operating elements:	items BC, BC inox

## PROPER DISASSEMBLY

When some parts or all of the panic bar needs to be replaced, the general guideline is to reverse the order of the original installation instructions. To replace the lock, all parts of the panic bar in the locking device zone must be disassembled, including the external plate. The lock itself (24) can be removed by unscrewing the two frontal screws.

FOR REPLACEMENTS USE ORIGINAL NINZ REPLACEMENT PARTS FROM ITS FULL CERTIFIED SYSTEM ONLY!

This operation should be carried out with great care in order not to damage or move the components located inside lock housing!

MAINTENANCE date	RECORD description of the intervention	release force checked	operator
		· ••••••••••••••••••••••••••••••••••••	•••••••
		-	

These instructions should be given to the owner of the activity, who must preserve them as a record of the maintenance operations carried out on the panic bar.