

NINZ S.p.A. - corso Trento, 2/A I-38061 ALA (TN) / ITALY www.ninz.it Tel. + 39 0 464 678300 Fax. +39 0 464 679025 info@ninz.it

SLASH ALU BMC

PANIC EXIT DEVICE for emergency exits A222-GB

5001319/2 - 01/24

	Commercial codes SLASH ALU BMC Pro (without hole cover pl SLASH ALU BMC		item 4201101.154 item 4201101.153	DoP no. Website Classification	1125-SL-01 https://www.ninz.it/it/download/dop 3 7 7 B 1 3 2 2 B A		
CE	Name and address of the producer		corso Trento 2/A A (TN) - ITALY	2 nd Character - grad 3 rd Character - grad	le 3 - Category of use: high frequency le 7 - Durability: 200.000 cycles le 7 - Mass of the door: over 200kg		
	Year application trademark	2007		5 th Character - grad 6 th Character - grad	 Suitable for use on fire/smoke rated doors Safety: suitable for emergency exits Highly resistant to corrosion 96h Safety of goods: 1000N 		
	Standard	EN 1125:2008 + EC1:2009		8 th Character - grad 9 th Character - grad	le 2 - Protrusion of the device: up to 100mm le B - Activation type: touch bar le A - Suitable for 1 or 2 leaved door		
	Certification authority nr.	0425			Suitable for doors with one leaf or for the active (first opening) leaf of two-leaved		
	CE certification number	0425-CPR-	001308	•	880 mm/leaf in size, a mass of up to 300 kg/leaf, mounted , fire resistant up to El_120 - REI120 and smoke proof. t bar: 75mm.		

SYMBOLS EMPLOYED



CAUTION

Indicates a danger that threatens people and/or material goods. Failure to observe the warnings indicated by this symbol may have serious consequences, such as personal injury and property damage.



ATTENTION

Indicates a danger that threatens material goods. Failure to observe the warnings indicated by this symbol may result in damage to material goods.

⇒ NOTICE

Warnings related to important technical aspects.

PRODUCT DESCRIPTION

Panic bar for one-leaved doors or for the active leaf of two-leaved doors located at emergency exits and activated by touch-bar. Composed of galvanized steel controls, chrome-polished aluminium carter, horizontal aluminium bar and stainless steel lever handle with galvanized steel installation plate.

This product does not contain or release any hazardous materials, as per UNI EN standard no. 1125 appendix ZA.

OPERATION MODE

From the pull-side (handle side) the door can be opened at any time whereas from the push-side opening is always possible by using the horizontal bar of the SLASH ALU BMC panic exit device.

WARNINGS

The SLASH panic bar activated by means of a horizontal bar is intended for use onto doors installed in escape routes where panic situations could develop. The safety features of this product are of fundamental importance to ensure its conformity with EN 1125. It is strictly forbidden to introduce any type of modifications apart from those described in these installation instructions.

RECOMMENDATIONS

In order to ensure that the panic bar could provide a high level of safety toward people and appropriate safety level toward goods, it should only be mounted onto doors and doorframes that are in good conditions. The door itself, therefore, should be checked to ensure that it was installed properly and that nothing obstructs its normal movement.

If rebate sealing are mounted on the door, make sure they do not inhibit proper functioning of the panic bar.



In case of two-leaved door where both leaves are equipped with panic bar, it is mandatory to check that each leaf opens when its respective panic bar is activated, and that leaves open freely when the bars are activated simultaneously.

The fastening instructions in the present document should be followed scrupulously during installation. Once installation is complete, the installer should give this document to the owner of the activity.

The horizontal bar should be installed in a way that maximizes its useable length.

For securing the door in the closed position, do not employ any other latching devices than those specified in the present document. This does not preclude the installation of automatic closing devices.

Different external access devices than those found on the list of certified components on pages 4/4 are considered unacceptable.


The SLASH panic bar is also designed for installation on hollow metal doors with an internal cell structure.

If a door closer is needed to return the door to the closed position, care should be taken not to make the opening step more difficult for children, the elderly and the disabled.

A pictogram (arrow) should be positioned immediately above the horizontal bar on the internal side of the door.



All of the included components described herein must be positioned and mounted in conformity with the present document.



CONTENTS OF THE SLASH ALU BMC PANIC BAR PACKAGE

position	pcs.	description	position	pcs.	description
1, 2	01	Slash mechanism assembly	19	01	Pan head self-tapping screw, Ø4,8x50mm (Proget+Univer)
3, 4	01	Slash ALU carter set			or Ø4,8x38mm (Rever)
5	01	Guide for connection pipe	20	05	Pan head self tapping screw Ø4,8x16mm
6	01	Connection pipe	21	08	M5 toothed washer
7	02	Protection	22	02	Black cap hole Ø8,8mm
8	01	Horizontal bar in anodized aluminium	23	02	Pan head self tapping screw Ø4,2x13mm
9	01	S3 hex key	24	01	S2 hex key
10	01	Adhesive pictogram (green arrow)	28 *	01	Hole-covering base plate
12	01	Stainless steel handle with galvanized steel installation plate	29 *	01	Cover for hole-covering base plate – black
		and fastening socket set screw	30 *	06	Self-drilling countersunk screw Ø4,2x16mm
13	01	Blank cover plate in stainless steel	32	02	M3x8mm pan head screw
14, 15	01	Square spindle 9x9x(55+40)mm	-	01	A034 hole-drilling template
16	01	M5 screw for threaded square spindle	-	01	Slash ALU BMC panic bar set installation instruction
17	02	Self-tapping countersunk screw Ø5,5x38mm			
18	02	M6 toothed washer			anic lock (26) and the respective strike box (counterstrike) (27) livered already mounted on the door as well as the subplate (25)!

Please note that article 4 of the MD of 03 November 2004 obliges the installer to write up, sign and provide the owner of the activity with a declaration of proper installation that makes explicit reference to the instructions supplied by the exit device manufacturer.

are delivered already mounted on the door as well as the subplate (25)!

TOOLS REQUIRED

Medium-sized Philips-head screwdriver or electric screwdriver, electric drill with Ø2 and Ø3mm drill bit for steel, fine-toothed and for aluminium hack-saws.

IMPORTANT

- Installation should be carried out by qualified personnel only and in strict conformity with the instructions supplied.
- For a correct installation all supplied components must be used, including toothed washers.
- No variations are allowed, and only components indicated in the package contents may be used.
- Given its purpose, the Slash ALU BMC panic bar should be mounted on the push-side of the door.
- Before proceeding with installation, check the package contents to ensure that no pieces are missing.
- Check if the door is equipped with the panic safe lock and the subplate (25).
- Check the type of lever handle to apply and follow the specific instructions.
- Any different installation configuration from that illustrated on page 2/4 is not allowed.

INSTALLATION

- For Rever door adjust the threaded square spindle (14) reducing its length for 5mm; be careful to cut the bevelled side.
- Insert the square spindles (14 and 15) into the lock and connect them with the respective screw (16) and fasten it. If the hole of the subplate (25) does not match with the square spindle, remove the lock and turn the subplate upside down.
- Screw onto installation plate of stainless steel handle (12) the screws (32), just enough to insert the cover plate (13).
- Approach the handle (12) to the leaf from pull-side taking care to centre the square spindle and fasten it with the screws (17) and their toothed washers (18) by centering the respective holes of the subplate (25).
- Use the template to drill the holes (31) with the Ø3mm drill bit, checking the level. If holes are already present, drill them again for the internal reinforcement.
- Insert the operating mechanism (1) of the panic bar over the square spindle (14), to the lock-side (push-side of the door), with the lift of the cam (1a) turned downwards. Fasten the mechanism starting with the two Ø4,8x16mm screws (20), then with the Ø4,8x50mm (Proget/Univer) or Ø4,8x38mm (Rever) screw (19), with their toothed washers (21).
- In case of Univer and Rever doors, apply the hole-covering base plate (28) after having provisionally clipped on the carter (3) on the mechanism. Center it vertically above the carter and at a distance of 30mm from the edge of the leaf (see drawing). Fasten the hole-covering base plate provisionally with the two more external screws (30) by first drilling holes in the metal panel with the Ø2mm drill bit, then positioning the cover (29) to verify that it attaches correctly without interfering with the carter. If everything matches, complete fastening with the remaining screws (30) after removing the cover (29) and the carter (3).
- Fasten the mechanism (2) of the panic bar at hinged side, using the selftapping screws Ø4,8x16mm (20) and their toothed washers (21).
- Make a precise "L" measurement, cut the aluminium bar (8), and remove the burrs from the cut edge. Insert the guide (5) for the connection pipe in the center of the bar.
- Take out the mechanism (2) in order to insert the horizontal bar (8) in the operating mechanism (1); then insert also the connection pipe (6).
- Insert the carters in the horizontal bar, first the one with the sticker (3), then the other one without (4). Join the bar with the hinged side mechanism (2) inserting also the connection pipe (6) before refastening the mechanism at the door. The flattened side of the pipe (6) has to be inserted from hinge side.
- Fasten the connection pipe (6) from the hinge side inserting the blocking pin (6b) in the provided hole in the connection pipe (6) and fastening with the 2 seeger rings (6c).
- Maintaining pulled the horizontal bar (8) cut the connection pipe (6) leaving it protruding for about 5mm from the operating bar (8). Insert then the pin (6a) in the connection pipe by means of the hexagonal key S3 (9). The pin has to be fastened until the holes for the blocking pin (6b) are centered. Insert then the bloking pin (6b) in the hole of the connection pin (6a) and fastening it with the 2 seeger rings (6c).
- Insert the protections (7) in the designated guides of both mechanisms.
- Apply the carters (3 and 4) on the relative mechanisms while ensuring that the
 protections (7) remain in their position. Clip on the carters by pushing softly the
 horizontal bar; first the narrow side, then the wide side. Finally fix the carters
 fastening their socket set screw without forcing, using the S2 hex key (24).

- Insert the two caps (22) in the open holes of the panic safe lock (26).



 Push the Slash ALU BMC panic bar at any point along the horizontal bar, checking to ensure that the latch bolt of the lock opens easily and fully. Use the same method to check the external handle. Test the door in both open and closed positions and if necessary, file down the plastic strike box (27) of one-leaved doors or the panic safe lock for inactive leaf of two-leaved doors.

- Fasten the installation plate of stainless steel handle (12) using the Ø4,2x13mm self-tapping screws (23) and their toothed washers (21) after drilling holes in the metal panel with the Ø2mm drill bit. Insert the cover (13) onto the handle (drw. 2). Using the S2 hex key (24) to unscrew the screws (32) until the cover become fixed, avoiding any deformations (drw. 3). Insert and fasten the socket set screw well with the S3 hex key (9).
- If present, the cover (27) has to be clipped on manually at the hole-covering base plate (26).
- Apply the pictogram (10) with the green arrow on the internal surface of the door, just above the horizontal bar.
- Lastly, use a dynamometer to measure the force required on the horizontal bar to release the lock. Record this force measurement in the present document.


USE

- Ensure that the door always opens easily.
- Avoid unnecessary strains on or handling onto handle and exit bar.
- Protect the panic bar from external atmospheric agents.
- Ensure that nothing hinders the free movement of the horizontal bar.
- Do not paint the lock.
- Use the bar properly, do not pull it in the wrong direction.
 - Δ Make sure that any damaged or malfunctioning parts are replaced immediately.

MAINTENANCE

To ensure that door usage conforms with regulations, the following maintenance checks should be carried out at least once a month:

- Confirm that all of the installed components correspond with those listed in the present instructions and that no other latching devices than those originally installed have been added to the door.
- Inspect and activate the panic bar to verify that all of its components are in satisfactory operational condition.
- Use a dynamometer to confirm that the release force shows no significant differences from the forces recorded at the time of installation.
 - Check whether all screws are fully tightened, tightening any that may have loosened.
- Check whether panic bar and handle can be moved with minimal effort, and that the latch bolt of the safe lock retreats from the strike box without offering resistance. If the door has become difficult to open due to friction, the resistance can be reduced by filing the strike box down to the appropriate height.
- Activate the Slash ALU BMC panic bar at both ends of the horizontal bar, checking to ensure full retraction of the latch bolt in both cases.
- Ensure that the latch bolt exits completely when the horizontal bar is released.
- Check the horizontal bar and replace it if any damage or deformities are detected.



- This product requires no special maintenance. Grease spray should be used to lubricate the internal workings of lock, handle and panic bar on a regular basis – the latter has a hole on its carter for this purpose.
- For normal cleaning use a cleaning agent designed specifically for chromepolished surfaces for the horizontal bar and another one designed specifically for stainless steel for the handle.



 Any adjustments that become necessary must be carried out by qualified personnel using original NINZ replacement parts.

 The owner of the activity is responsible for keeping the declaration of correct installation on file, conducting proper panic bar maintenance in accordance with all of the manufacturer's maintenance guidelines, keeping maintenance and check-up records and preserving the present document.

ICIM S.p.A Identification number: 0425 Piazza Don Emrico Mapelli, 75 - 20099 Sesto San Giovanni (MI) - ITALY Certificato di costanza delle prestazioni Certificate of constancy of performance
Piazza Don Enrico Mapelli, 75 - 20099 Sesto San Giovanni (MI) - ITALY Certificato di costanza delle prestazioni
Piazza Don Enrico Mapelli, 75 - 20099 Sesto San Giovanni (MI) - ITALY Certificato di costanza delle prestazioni
Certificato di costanza delle prestazioni
· ·
Continuate of constancy of performance
Certificato N. Certificate No. 0425 - CPR - 001308
In conformità ai Regolamento 3050011EL del Parlamento Europeo e del Contaglio del 9 marzo 2011 Regolamento Produtti da del complanzo sello Regolamento 3050011EL del Parlamento Factoria del 19 Mancho 2011 del 2011 (el Construction In complanzo sello Regolamento 3050011EL del del Europeano Parlamento and di 19 Mancho 2011 del 2011 (el Construction Producto Centificano del Cello del Centoria del 19 Mancho 2011 del
Dispositivi per le uscite antipanico azionati mediante una barra orizzontale per l'utilizzo
sulle vie di esodo Panic exit devices operated by a horizontal bar, for use on escape routes
SERIE / SERIES SLASH, SLASH AR, SLASH ALU, SLASH ALU AR, SLASH INOX, SLASH INOX AR
MODELLI/MODELS Si veda allegato / See annex Caratteristiche: vedi Allegato / Characteristics: see Annex
IMMESSO SUL MERCATO CON IL NOME O IL MARCHIO DI PLACED ON THE MARRET UNDER THE NAME OR TRADE MARK OF
NINZ S.p.A.
SEDE LEGALE HEAD OFFICE Corso Trento, 2/A - 38061 ALA (TN) - ITALY
UNITÀ OPERATIVA PRODUCTIVN UNIT Corso Trento, 2/A - 38061 ALA (TN) - ITALY
Duesto certificato attesta che tutte la disposizioni riguardanti la valutazione e la verifica della costanza della prestazione e la pretazioni discritto nel traggiato 24 della crista. reformanza discritto nel Anno 24 del teto tecnologno per essessment and verification of constancy of performance and the performance advance in Anno 24 del teto tecnologno per essessment and verification of constancy of performance and the performance advance in Anno 24 del teto tecnologno per essessment and verification of constancy of performance and the performance advance in Anno 24 del teto tecnologno per essessment and verification of constancy of performance and the performance advance in Anno 24 del teto tecnologno per essessment and verification of constancy of performance and the performance advance in Anno 24 del teto tecnologno per essessment and verification of constancy of performance and the performance advance in Anno 24 del teto tecnologno per essessment and verification of constancy of performance and the performance advance in Anno 24 del teto tecnologno per essessment and verification of constancy of performance and the performance advance in Anno 24 del teto tecnologno per essessment and verification of constancy of performance and the performance advance in Anno 24 del teto tecnologno per essessment and verification of constancy of performance and tecnologno per essessment and per essessment and per e
EN 1155/2008 + EC1:2009 enflambito del sistema 1 di cui al presente comficato vengene apolicate e che il controlto di produzione in tabirica condotto dal produttore e valutato al fino di prarrette ia under signiter 3 red cui finito critticate an exploide and finite file foctory productione contotic conducted by the manufacturer is assessed
to ensure the COSTANZA DELLA PRESTAZIONE DEL PRODOTTO DA COSTRUZIONE
CONSTANCY OF PERFORMANCE OF THE CONSTRUCTION PRODUCT Questo certificato è stato emesso per la prima volta il 31/05/2007 e ha validità sino a che la norma armonizzata, il prodotto da
contractions, in medip AUVP e be contractionin if graduations real establishments non subsenson modificate significative, o sino a che non vergan sorgeno or dinal diarginario di cultarizzative modificatio (NS g.A. This certificate was first lassed on 31/05/2007 and will remain visió as long as neither the hemonited standard the construction product. The AVCP methods not the modulaturing conditions in the plant are modified significantity, unless suspended or withdrawn by the radiated product and standard standard standard standard standard standard standard to withdrawn by the radiated product of standard standard standard standard standard standard standard standard standard to withdrawn by the radiated product difficult to by (S.B. g.A.
Il presente Certificato è da ritenersi valido solo se accompagniato dal relativo Allegato / This Certificate is valid only with the relative Amex
y lup
ICIM S.p.A. Direttore Tecnico
EMISSIONE
22/06/2017

SPARE PARTS (see exploded drawing at page 2/4)					
position	code	description			
1, 2, 3, 4, 5	, 7, 10 3102064	.001 Slash ALU latch	case		
1, 2	3105119	.001 Slash assembly	mechanism		
3, 4	3105173	.001 Slash ALU carte	er set		
5, 7	3105130	.001 Slash 2 protecti set	ons + 1 plastic piece		
6, 8	4204010	Anodized or pai set	nted aluminium bar		
9, 12, 13, 1 16, 17, 18, 21, 22, 23,	19, 20,	024 Slash BMC set	- stainless steel		
25	3407013	.001 Reinforcement	olate		
26	3201001	.016 Panic safe lock	to push (AP 16/18)		
27	4212024	.001 Set of 10 Proge	t strike box lock		
27	4212025	.001 Set of 10 Univer	thk60 strike box lock		
27	4212026	.001 Set of 10 Unive	r thk50 strike box lock		
27	4212027	.001 Set of 10 Rever	strike box lock		
* 28, 29, 30	4204020	.002 Slash hole cove screws – finishi	r + base plate + ng: black		

Certified components for SLASH ALU BMC

Panic exit device:	model "SLASH ALU"
Panic safe lock:	item AP 16/18
Lock strike boxes:	items 2401006, 2401005, 2401015, 2401014
Operating element:	item BMC inox

FOR REPLACEMENTS USE ORIGINAL NINZ REPLACEMENT PARTS FROM ITS FULL CERTIFIED SYSTEM ONLY!

PROPER DISASSEMBLY

When some parts or all of the panic bar needs to be replaced, the general guideline is to reverse the order of the original installation instructions. To replace the lock, all parts of the panic bar in the locking device zone must be discourse handle. The lock itself (26) can be

be disassembled, including the external handle. The lock itself (26) can be removed by unscrewing the two frontal screws.

This operation should be carried out with great care in order not to damage or move the components located inside lock housing!

MAINTENANCE date	RECORD description of the intervention	release force checked	operator
	-		
	-		
	·		

These instructions should be given to the owner of the activity, who must preserve them as a record of the maintenance operations carried out on the panic bar.